

Materials Listing
Molding Privy
3/3/2006

Connectors

Model	Count	Unit Cost	Cost	Use
A44	12	\$2.57	\$30.84	Secure rails to columns
BC4Z	18	\$4.97	\$89.46	Secure columns to crib. Use 3 per column
DJT14Z	12	\$1.73	\$20.76	Secure Panels to columns
LUS44Z	8	\$1.15	\$9.20	Joist Hangers for 4x4s
LUS24Z	4	\$0.72	\$2.88	Joist Hangers for 2x4s
AC4Z	12	\$5.43	\$65.16	Secure roof 4x4 to columns
H2.5AZ	24	\$0.48	\$11.52	Secure rafters to roof 4x4s
			\$0.00	
Total Connectors			\$229.82	

Wood Materials

4x4x12'	35	\$13.97	\$488.95
4x4x8'	4	\$6.97	\$27.88
Plywood 3/4x4x8	7	\$37.97	\$265.79
Plywood 1/2x4x8	4	\$27.97	\$111.88
2x4x8'	12	\$2.97	\$35.64
1x6x12'	14	\$6.97	\$97.58
1x4x12'	7	\$4.69	\$32.83

Total Wood **\$1,060.55**

Accessories

Grab Bar	2	\$40.00	\$80.00
Toilet Riser with Lid	1	\$225.00	\$225.00
Screws	2	\$30.00	\$60.00
Roofing-Metal	1	\$150.00	\$150.00

Total Accessories **\$515.00**

Total Cost **\$1,805.37**

Materials Prices as of 3/3/2006 from Home Depot, Midtown Atlanta